

**Monitor costing systems on medium rise building
and construction projects
CPCCB5002A**

Assignment No 1

Assignment Overview

This Assignment relates to the following Project:

Project 2 Medium Rise Apartments

Job Address: 2135 The Boulevard, Strathfield, NSW

Job Title: Proposed Commercial and Residential Development

Client: AKM Developments

Architect: Olympic Designs, 55 Olympic Pde, Homebush, NSW

You should obtain the following documents, from the OLS, for the job:

Plans:	Page 1 – Site Plan
	Page 2 – Basement 1
	Page 3 – Basement 2
	Page 4 - Basement 1 Setout
	Page 5 - Basement 2 Setout
	Page 6 – Floor Plan Level 1
	Page 7 - Floor Plan Level 2
	Page 8 - Floor Plan Level 3
	Page 9 - Floor Plan Level 4
	Page 10 - Floor Plan Level 5
	Page 11 – Setout Level 1 and 2
	Page 12 - Setout Level 3 and 4
	Page 13 - Setout Level 5
	Page 14 – South Elevation
	Page 15 - North Elevation
	Page 16 – East and West Elevations
Bill of Quantities:	Preliminary Estimate (6 pages)
Specification of Works	(60 pages)

Question 1

Use the following information to prepare a Precedence Diagram to establish Early Start/Early Finish, Late Start/Late Finish, and Float and identify the critical path.

You can prepare the diagram manually or using a computer program such as Microsoft Project. You should use a 5 day calendar to allow for the fact that this is a preliminary estimate. The project will work on a 6 day schedule once construction starts and this will provide a contingency allowance for the project.

The project is scheduled to start on 13th January 2014.

PROGRAM ACTIVITY SCHEDULE

ID	Task Name	Duration	Predecessors
1	Job Duration	255 days	
2	Start	0 days	
3	Preliminaries	Whole of Job	2
4	Groundworks	20 days	3
5	Concrete	155 days	
6	Concrete Basement 2	17 days	4,36,51
7	Concrete Basement 1	16 days	6,14
8	Concrete Level 1	22 days	7,15
9	Concrete Level 2	15 days	8,24,16
10	Concrete Level 3	13 days	9,25,17
11	Concrete Level 4	14 days	10,26,18
12	Concrete Level 5	15 days	4,11,27,19
13	Masonry	144 days	
14	Masonry Basement 2	6 days	6
15	Masonry Basement 1	4 days	14,7
16	Masonry Level 1	11 days	15,8
17	Masonry Level 2	8 days	16,9

18	Masonry Level 3	6 days	17,10
19	Masonry Level 4	8 days	18,11
20	Masonry Level 5	6 days	19,12
21	Metalwork	197 days	
22	Metalwork Basement 2	2 days	6,14SS+1 day
23	Metalwork Basement 1	2 days	22,15SS+1 day
24	Metalwork level 1 Windows and Doors	3 days	23,16SS+1 day
25	Metalwork level 2 Windows and Doors	3 days	24,17SS+1 day
26	Metalwork level 3 Windows and Doors	3 days	25,18SS+1 day
27	Metalwork level 4 Windows and Doors	3 days	26,19SS+1 day
28	Metalwork level 5 Windows and Doors	3 days	27,20SS+1 day
29	Metalwork level 1 Fitout	3 days	93,115
30	Metalwork level 2 Fitout	3 days	29,94,116
31	Metalwork level 3 Fitout	3 days	30,95,117
32	Metalwork level 4 Fitout	3 days	31,96,118
33	Metalwork level 5 Fitout	3 days	32,97,119
34	Hydraulics	224 days	
35	Hydraulics Rough In Sub basement	7 days	4
36	Hydraulics Rough In Basement 2	7 days	4
37	Hydraulics Rough In Basement 1	7 days	36,6
38	Hydraulics Rough In Level 1	7 days	37,7
39	Hydraulics Rough In Level 2	7 days	38,8
40	Hydraulics Rough In Level 3	7 days	39,9

41	Hydraulics Rough In Level 4	7 days	40,10
42	Hydraulics Rough In Level 5	7 days	41,11
43	Hydraulics Fitoff Basement 2	5 days	115,42
44	Hydraulics Fitoff Basement 1	5 days	43,115
45	Hydraulics Fitoff Level 1	5 days	44,115
46	Hydraulics Fitoff Level 2	5 days	45,116
47	Hydraulics Fitoff Level 3	5 days	46,117
48	Hydraulics Fitoff Level 4	5 days	47,118
49	Hydraulics Fitoff Level 5	5 days	36,7,89,97,48,119
50	Electrical	221 days	
51	Electrical Rough in Below Basement Level	3 days	4
52	Electrical Rough in Basement 2	2 days	51,14
53	Electrical Rough in Basement 1	2 days	52,15
54	Electrical Rough in Level 1	2 days	53,16
55	Electrical Rough in Level 2	2 days	54,17
56	Electrical Rough in Level 3	2 days	55,18
57	Electrical Rough in Level 4	2 days	56,19
58	Electrical Rough in Level 5	2 days	57,20
59	Electrical Fitoff Basement 2	2 days	52,91,58
60	Electrical Fitoff Basement 1	2 days	59,53,92
61	Electrical Fitoff Level 1	2 days	60,54,115
62	Electrical Fitoff Level 2	2 days	61,55,116
63	Electrical Fitoff Level 3	2 days	62,56,117

64	Electrical Fitoff Level 4	2 days	63,57,118
65	Electrical Fitoff Level 5	2 days	64,58,119
66	Mechanical	138 days	
67	Mechanical Rough in Lift	5 days	7
68	Mechanical Fitoff Lift	3 days	67,97
69	Mechanical Rough in AC to Basement 2	2 days	7
70	Mechanical Rough in AC to Basement 1	2 days	69,8
71	Mechanical Rough in AC to Level 1	2 days	70,9
72	Mechanical Rough in AC to Level 2	2 days	71,10
73	Mechanical Rough in AC to Level 3	2 days	72,11
74	Mechanical Rough in AC to Level 4	2 days	73,12
75	Mechanical Rough in AC to Level 5	2 days	74,13
76	Mechanical Fitoff to Basement 2	2 days	91,75
77	Mechanical Fitoff to Basement 1	2 days	76,92
78	Mechanical Fitoff to Level 1	2 days	77,93
79	Mechanical Fitoff to Level 2	2 days	78,94
80	Mechanical Fitoff to Level 3	2 days	79,95
81	Mechanical Fitoff to Level 4	2 days	80,96
82	Mechanical Fitoff to Level 5	2 days	81,97
83	Waterproofing	87 days	
84	Waterproofing to Level 1	2 days	93FS+5 days
85	Waterproofing to Level 2	2 days	84,94FS+5 days
86	Waterproofing to Level 3	2 days	85,95FS+5 days

87	Waterproofing to Level 4	2 days	86,96FS+5 days
88	Waterproofing to Level 5	2 days	87,97FS+5 days
89	Roofer	7 days	12,20
90	Plasterer	143 days	
91	Plasterer to Basement 2	3 days	14,52
92	Plasterer to Basement 1	3 days	91,53
93	Plasterer to Level 1	5 days	92,54
94	Plasterer to Level 2	5 days	93,55
95	Plasterer to Level 3	5 days	94,56
96	Plasterer to Level 4	5 days	95,57
97	Plasterer to Level 5	5 days	96,58
98	Carpenter Fitout	19 days	
99	Carpenter Fitout to Basement 2	2 days	76
100	Carpenter Fitout to Basement 1	2 days	99,77
101	Carpenter Fitout to Level 1	3 days	100,78
102	Carpenter Fitout to Level 2	3 days	101,79
103	Carpenter Fitout to Level 3	3 days	102,80
104	Carpenter Fitout to Level 4	3 days	103,81
105	Carpenter Fitout to Level 5	3 days	104,82
106	Painter	53 days	
107	Painter to Basement 2	3 days	59
108	Painter to Basement 1	3 days	107,60
109	Painter to Level 1	4 days	108,61

110	Painter to Level 2	4 days	109,62
111	Painter to Level 3	4 days	110,63
112	Painter to Level 4	4 days	111,64
113	Painter to Level 5	4 days	112,65
114	Ceramic Tiler	40 days	
115	Ceramic Tiler to Level 1	8 days	101,84FS+5 days
116	Ceramic Tiler to Level 2	8 days	115,102,85FS+5 days
117	Ceramic Tiler to Level 3	8 days	116,103,86FS+5 days
118	Ceramic Tiler to Level 4	8 days	117,104,87FS+5 days
119	Ceramic Tiler to Level 5	8 days	118,105,88FS+5 days
120	Carpet	40 days	
121	Carpet to Level 1	8 days	109
122	Carpet to Level 2	8 days	121,110
123	Carpet to Level 3	8 days	122,111
124	Carpet to Level 4	8 days	123,112
125	Carpet to Level 5	8 days	124,113
126	Cleaner	33 days	
127	Cleaner to Basement 2	1 day	109,121
128	Cleaner to Basement 1	1 day	109,121
129	Cleaner to Level 1	1 day	109,121
130	Cleaner to Level 2	1 day	129,110,122
131	Cleaner to Level 3	1 day	130,111,123
132	Cleaner to Level 4	1 day	131,112,124

133	Cleaner to Level 5	1 day	132,113,125
134	External Works	21 days	97
135	Finish	0 days	133,134

Question 2

Using the Bill of Quantities for the Preliminary Estimate, allocate the costs for each activity and create an S-Curve for the job based on the activities Early Start dates.

Note:

- You will need to allocate the PC ITEMS to the relevant activities.
- The Preliminaries will be allocated across the entire duration of the project.

Question 3

Collate the S-Curve costs into monthly summaries and prepare a cash flow statement to determine the capital required for the job.

Expenditure	Month 1	=	\$ _____
	Month 2	=	\$ _____
	Month 3	=	\$ _____
	Month 4	=	\$ _____
	Month 5	=	\$ _____
	Month 6	=	\$ _____
	Month 7	=	\$ _____
	Month 8	=	\$ _____
	Month 9	=	\$ _____
	Month 10	=	\$ _____
	Month 11	=	\$ _____
	Month 12	=	\$ _____

Use the following information to create your cash flow statement:

Profit and Overhead	=	18%
Defects Liability Period	=	Twelve (12) weeks.
Cost of Finance	=	12% per annum, To be entered the month after any negative Cumulative Total.
Frequency of Claims	=	At the end of each four (4) weeks.
Period of Payment	=	Four [4] weeks between claim and payment.
Deposit	=	5% of Contract Sum To be included as additional income in Month 1, and then deducted from the first Progress Claim.
Initial Project Float	=	\$ 300,000.00 To be included as additional income in Month 1, and then deducted any time after the Cumulative Total (Progress Account) is trading positive.
Bank Guarantee	=	Two (2) x 8% of Contract Sum

Use the template over the page to calculate your costs:

Cash Flow Chart		Note: All figures to be entered in multiples of \$1,000.00 (to two [2] decimal places).														
		All Outgoings (inc. Interest, Direct Project Costs and Retention) are to be shown in Brackets, i.e. [\$]														
		Four (4) Weeks = One (1) Month														
		Contract Sum														
		Total (Maximum) Retention Held														
Month		1	2	3	4	5	6	7	8	9	10	11	12			
Expend	- Direct Project costs															
	- Interest															
Sub - Total																
Income	- Float															
	- cash deposit															
	- P'claim (Gross)															
	- deposit deducted															
	- retention deducted															
	- retention returned															
	- float returned															
Sub - Total																
Total per period																
Cumulative total																
Interest																
Interest	per year															
Interest	per month															